# PROJECT SHEET – SADLIERS CROSSING

**PROJECT OVERVIEW**

Replacement of life expired bridge sections

Steel girder transom sections replaced by ballasted deck bridge beams

**PROJECT DETAILS:**

| | |
|---|---|
| **Start Date** | **Sept' 2015** |
| **Completion Date** | **June 2016** |
| **Contract Type** | **Fixed Price** |

**Replacement of railway ladder with Sekisui FFU composite bearers**

**Life expired concrete turnouts**

**SCOPE OF WORKS**

**The construction works for the project included**

- **Headstock replacement**
- **Transom replacement**
- **Quad-I Girder installation**
- **Approach formation Treatment**
- **Rail replacement**
- **Quality works (Weld/adjust/resurface/heights & staggers)**